



Public Works | Engineering

44 East Downer Place | Aurora, IL 60507

Phone: (630) 256-3208 | Fax: (630) 256-3229 | Web: www.aurora.il.us

2026 Cold Weather Hot-Mix Asphalt Requirements

The City of Aurora asphalt cutoff date is **October 30, 2026**. Variations beyond this date will be considered if the following conditions are met:

All asphalt placements beyond that date must be requested in writing to the attention of the City of Aurora Engineering Division Assistant City Engineer, and may be submitted via email to: EngGenMail@aurora.il.us or FAX (630) 256-3229. These requests must provide the following information to be considered:

Submit a 1 day forecast, showing both daytime temperature of 45 degrees, and rising, from the time of asphalt placement.

Include Contractor's name, Contractor's phone number, Customer's name, Customer's address and Customer's phone number.

If your request is approved then you may need to provide the following:

1. Density Testing:

Any actual temperatures below 45 degrees, between time of placement and final compaction, will require independent certification, from a testing firm such as Terracon Consultants Inc., or TSC (Testing Service Corporation), shall be obtained.

2. Required in all cases - Pre Placement Inspection:

Call the City a minimum of 24 hours in advance to schedule the required pre-pour inspection. (630) 256-3208

These additional measures are the responsibility of the individuals requesting the variance. Any reports resulting from these measures shall be submitted to the City of Aurora Engineering Division under cover letter indicating the address, and date of the asphalt placement.